Bruhath Bangalore Mahanagara Palike

16

Office of the Executive Engineer
Electrical Division, Dasarahalli Zone
Bruhath Bengaluru Mahanagara Palike

"DTS for Kind Approval"

Name of the Work:-Providing sodium vapour street light fittings , control switches and control wires at various ward in Dasarahalli zone.

Sl. No.	Approved Qty	Description	Unit	Approved Rates		Rate quoted by contractor	
				in Figures	in words	in Figures	in words
		KPWD (Ele) S.R.2010-11					
1	150.00	Supplying High Pressure Sodium vapour street light fitting die Cast aluminium Canopy With aluminum housing for control gear, finished stove enamel gray glassy white canopy interior with a pair of anodized aluminum reflectors with toughened flat glass, gasket lining for drip inseat resistance duly wired with porcelain holder copper choke, igniter and HPF condenser including a sodium vapour lamp. I) 250 Watts a)Group'A' Make :Philips, Wipro, Hevells, Bajaj, Surya,CG,Schreder,Hallonix	Each	6150.00	Rupees Six Thousand One Hundred and Fifty Only		
2	150.00	Supplying & fixing of.....mm dia class A G1 pipe bracket upto 2 mtrs long bent at suitable angle and fixing to this btacket 1*40/2*40 Watts fluorescent tube street light fitting of all capacities to G1 or C1 or rail or RCC pole/Wall using suitable clamps,bolts, and nuts and wiring using suitable capacity wires complete a)using 32mm dia G1.pipe	Each	685.00	Rupees Six Hundred and Eighty Five Only		
3	5.00	Supply and erection of .....mtr RCC pole including earth work etc., complete as per the standard technical specification.	Each	6583.00	Rupees Six Thousand Five Hundred and Eighty Three Only		
4	150	Supply and fixing of ..... cross arm including all Hardwares compete as per the standard technical specification. b) 2 Pin 45x45x5mm-510mm	Each	123.00	Rupees One Hundred and Twenty Three Only		
	5	a) 4 Pin 45x45x5mm-1110mm	Each	229.00	Rupees Two Hundred and Twenty Nine Only		

5	160	Supplying and Fixing..... including all Hardwares etc complete as per the Standard technical Specification.	Each	70.00	Rupees Seventy Only		
	15	d) No.8 Strain Insulator	Each	24.00	Rupees Twenty Four Only		
6	3500	Supplying and stringing of ACSR Conductor (6/2.59mm Al+1/2.59mm steel)	Mtr	19.80	Rupees Nineteen Only Paise Eighty Only		
7	155	Supplying and fixing ..... including all Hardwares etc complete as per the standard technical specification	Each	61.00	Rupees Sixty One Only		
8	487500	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete b) 16 SWG	sqcm	0.33	Rupees Zero Only Paise Thirty Three Only		
9	65	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete. d) 100 Amps	Each	415.00	Rupees Four Hundred and Fifteen Only		
10	65	Supplying and fixing Microprocessor based Astronomical timer switch with using necessary bolts, nuts and washers etc.,	Each	7515.00	Rupees Seven Thousand Five Hundred and Fifteen Only		
11	65	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required.	Each	195.00	Rupees One Hundred and Ninety Five Only		
12	65	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.	Each	7450.00	Rupees Seven Thousand Four Hundred and Fifty Only		
13	130	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. . (32.9a)	Rmtr	240.00	Rupees Two Hundred and Forty Only		

14	260	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes	Each	14.00	Rupees Fourteen Only		
15	13	Supplying.....amps rated 3 phase with neutral bus bar using requirement capacity electrolytic aluminium strips covered with heat shrinkable coloured PVC sleeve, mounted on phenolic/FRP/DMC insulator which are mounted on	Rmtr	1600.00	Rupees One Thousand Six Hundred Only		
16	650	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV Class 4 core 16sqmm	Per Mtr	150.00	Rupees One Hundred and Fifty Only		
17	650	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required. I. In existing trench /duct.a. 6 sqmm to 16sqmm	Rmtr	8.00	Rupees Eight Only		

I am prepared to take up the above work at the rates quoted in the Schedule 'B'

CONTRACTOR

EXECUTIVE ENGINEER (Ele)
DASARAHALLI ZONE, BBMP

"DTS ಅಧಿಕಾರಿಯವರು
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.